



## COTTAGE GROVE ROAD 2016 ROADWAY CONSTRUCTION FACT SHEET



### **COTTAGE GROVE RD: LUMBERMANS TRAIL TO INTERSTATE HIGHWAY I39/90**

#### Work Schedule

The estimated completion date is September 1, 2016.

#### Scope of Work

This project will replace the water main between S. Stoughton Rd. and Ellen Avenue; replace the sanitary sewer main and laterals between Stoughton Rd. and Flora Lane including a dual main replacement between Acewood Blvd. and Flora Ln.; replacement of portions of the curb and sidewalk; milling off the asphalt surface and repaving with new asphalt.

Pedestrian activated flashing traffic signals will be installed at the intersections of Flora Ln, Meadowlark Ln, and Thompson Drive.

#### Traffic

Two-way traffic will be maintained on Cottage Grove Road, but there will only be one lane in each direction. All of the traffic will be shifted to the same side of the median while the contractor works on the other lanes. The intersection of Acewood Blvd. will remain open to traffic at all times. The contractor may need to close some intersections in order to perform their work, but they may not close adjacent intersections at the same time. Madison Metro buses will continue to operate on Cottage Grove Road.

#### Personnel

The City's Construction Inspector is Eric Hoel. He may be reached in the field, at 520-2384, in the office at 261-9972, or by email [ehoel@cityofmadison.com](mailto:ehoel@cityofmadison.com).

The City's Project Manager is LeAnne Hannan. She may be reached in the office at 266-4057 or by email [lhannan@cityofmadison.com](mailto:lhannan@cityofmadison.com).

### **COTTAGE GROVE RD: MONONA DRIVE TO DEMPSEY ROAD** **DEMPSEY ROAD: COTTAGE GROVE ROAD TO ANCHOR DRIVE**

#### Work Schedule

The estimated completion date is November 1, 2016.

### Scope of Work

Cottage Grove Road: New pavement, curb & drive aprons. Add medians/islands, improve cross walks and add turn lanes. Add parking lane north side between Royster Oaks and Dempsey.

Dempsey Road: New pavement, curb & drive aprons (North of railroad tracks, only limited curb and driveway replacement and curb on both sides south of Cottage Grove.

Sanitary Sewer: Replace existing mains, and replace laterals from the main to the property line. Some of the existing sanitary sewer main on Dempsey south of railroad tracks will not be replaced.

Water Main: Replace the existing water mains, and reconnect services to the new main. Water replace continues to the east past project limits, to approx. 175' east of Claire Street. Existing water main will not be replaced on Cottage Grove between Johns and Dempsey.

Storm Sewer: Replace and extend storm sewer.

Street Lights: Update street lighting w/ area lights.

### Traffic

Dempsey will be closed to through traffic (open to local traffic only) within the project limits. On Cottage Grove, two lanes (one lane in each direction) will be maintained throughout construction. Traffic will first be switched onto the southern part of the street, and then when construction of the northern lanes of the street is complete, traffic will be switched into the northern lanes. Buses will be detoured during construction.

### Personnel

The City's Construction Inspector is Eric Hoel. He may be reached in the field, at 520-2384, in the office at 261-9972, or by email [ehoel@cityofmadison.com](mailto:ehoel@cityofmadison.com).

The City's Project Manager is Lisa Coleman. She may be reached in the office at 266-4093 or by email [lcoleman@cityofmadison.com](mailto:lcoleman@cityofmadison.com).

### **ADDITIONAL ROADWAY CONSTRUCTION INFORMATION**

Roadway Project Website: <http://www.cityofmadison.com/engineering/projects/>

My Madison Account, sign-up for email updates: <https://my.cityofmadison.com/>



## **PROPOSED RECONSTRUCTION SCHEDULED FOR 2018** **Cottage Grove Road: Thompson Drive to Sprecher Road**

### **Purpose of Project**

- Replace the deteriorating asphalt pavement
- Provide two travel lanes in each direction for the length of project
- Provide improvements for pedestrian and bike access and safety
- Improve City underground utilities

### **Project Limits**

Approximately 350 feet east of I-39/90 to South Sprecher Rd (Phase 1)  
South Thompson Dr to approximately 350 east of I-39/90 (Phase 2)

### **Project Summary**

The proposed improvements consist of reconstructing Cottage Grove Road to a four lane, urban boulevard section. The proposed street layout will include two through lanes and a 5-foot wide bike lane in each direction, with a raised center median and left turn lanes at each intersection. Street Lighting will be added in the new medians and the existing traffic signals will be upgraded. Sidewalk will be added where it currently does not exist and any existing sidewalk that is in poor condition will be replaced to ensure ADA compliance. The proposed project will also include construction of water main and a new storm sewer system. Storm water treatment will be addressed with the construction of a retention pond and treatment swales in terrace areas. Street terrace trees will also be planted with the project.

The project will be constructed in two phases. The first phase of the project is scheduled for construction in 2018, and includes reconstruction of Cottage Grove Road from the east side of I-39/90 to South Sprecher Road. The second phase of construction includes the reconstruction of Cottage Grove Road from South Thompson Drive to the east side of I-39/90 and will include the replacement of the Cottage Grove Rd overpass of I-39/90. The construction year of the second phase of the project is not scheduled but is planned to coincide with the WisDOT's replacement of the I-39/90 overpass.

### **Traffic During Construction**

Cottage Grove Road will be reduced to one lane in each direction during Phase 1 of the project. Motorists will be shifted to one side of the street while work is completed on the opposite side. Temporary turn lanes and signals and will be provided at signalized intersections.

### **Right of Way**

Narrow strips of right-of-way will need to be acquired from three properties adjacent to the project in order to construct the new sidewalk. Strips of temporary limited easement will also be required along much the project for grading purposes.

### **Tree Removals and Trimming**

During construction, it will be necessary to remove trees and trim tree limbs and/or roots to accommodate the construction. Street trees will be replanted in terrace areas during construction of the project. A total of 25 trees and shrubs have been identified to be removed or relocated during construction.

### **Bus Service**

New bus boarding pads will be constructed with the project. Madison Metro Bus service will continue on Cottage Grove Road during construction. Temporary bus boarding areas will be provided to allow access to bus stops.

### **Preliminary Project Schedule**

Phase 1 work is planned to start in the spring of 2018 and be completed by September 1, 2018.

Phase 2 of the project (bridge replacement) is not currently scheduled. WisDOT is currently conducting an I-39/90 corridor study to determine needs to meet future traffic volumes.

### **Information & Contacts**

Project Website: <http://www.cityofmadison.com/engineering/projects/cottage-grove-road>

My Madison Account, sign-up for email updates: <https://my.cityofmadison.com/>

City Project Manager – Glen Yoerger, 261-9177 [gyoerger@cityofmadison.com](mailto:gyoerger@cityofmadison.com)

Traffic Engineering – Scott Langer, 266-5987 [slanger@cityofmadison.com](mailto:slanger@cityofmadison.com)